AUTOMATING INFRASTRUCTURE with ANSIBLE

Hands on presentation by matyas@justrocket.de

23. apr. 2018

In the beginning...

- Manual server setup
- Manual installation and configuration
- Heap of shell scripts



... there were problems...

- What is actually on the machine?
- Keeping track of installed versions & configurations
- Setting up new machines
- Everybody had his / her own way of doing things



... that needed to be solved...


- Structured Infrastructure managment
- Documented versioning
- Replayability of configurations
- Testability of installations
- Small learning curve



... by




- Straightforward setup
- Easy to learn
- Scalable
- Large team features
- Enterprise backing & support (\$)
- Large & active community





How does it work?





Key concepts

- **Inventory:** list of servers
- **Playbook:** describe how to set up servers
- Modules: the tools using which help you execute tasks




Inventory

```
all:
   hosts:
      backup:
            ansible_host: 192.168.123.123
            ansible_user: root
children:
      production_servers:
            hosts:
            mariadb:
            ansible_host: 192.168.123.123
            ansible_user: dbadmin
            nginx:
            ansible_host: 192.168.123.124
            ansible_user: appadmin
```



Playbooks and modules





Playbooks and modules

```
- name: User friendly description of play
hosts: all
tasks:
    - name: Install a file manager
    apt:
        package: mc
        state: present
    - name: Check out a project
    git:
        repo: git@gitlab.com:justrocket/dev
        accept_hostkey: yes
        dest: /opt/dev
```



Core Modules

```
Cloud / Clustering / Commands / Crypto

Database / Files / Identity / Inventory

Messaging / Monitoring / Net Tools / Network

Notification / Packaging / Remote Management

Source Control / Storage / System / Utilities

Web Infrastructure / Windows
```



Variables, basic loops



Shell module


```
- name: Init db cluster
hosts: mariadb_server
tasks:
    - name: Copy script to server
file:
     src: files/cluster_init_script.sh
     dest: /opt/scripts/cluster_init_script.sh
     - name: Run init script
shell: "/opt/scripts/cluster_init_script.sh"
```



Organizing: Tags



Organizing: Roles




DEMO

https://github.com/justrocket/ansible-presentation



Going Enterprise with Tower or AWX





Questions.

?



Thank you



email: matyas@justrocket.de

twitter: @albertmatyi

presentation:

git@github.com:justrocket/ansible-presentation.git

